



THE ANDHRA PRADESH STATE CO-OPERATIVE BANK Ltd.,

(A State Govt. Partnered Scheduled Bank)

HO: NTR Sahakara Bhavan, # 27-29-28, Governorpet, Vijayawada – 520 002
Dept. Name: Premises, Email-id: premises@apcob.org

Date: 21.01.2023

TENDER NOTICE

Interior works in APCOB Mangalagiri Branch

Sealed Quotations are invited from GST registered firms for undertaking interior works tabulated below in Mangalagiri Branch of The A.P. State Co-operative Bank Ltd., at Vijayawada.

Time Schedule:

Quotation calling date	-	21.01.2023
Quotation closing date	-	24.01.2023 up to 11: 00 AM
Quotation opening date	-	24.01.2023 at 11: 30 AM
Contact Person	-	DGM (GAD)

Note:

1. Valuation of work is subjected to actual measurements by Bank's consultant Civil Engineer.
2. Branch interior layout plan is enclosed.

If your firm is interested in participation and having its Registered/Branch Office at Vijayawada with AP GST No., please submit your quotation (inclusive of all taxes) to:

M Shyama Sundara Rao
DY. GENERAL MANAGER (GAD)
THE A.P. STATE CO.OPERATIVE BANK LTD.,
HO: NTR Sahakara Bhavan, # 27-29-28, Governorpet, Vijayawada-520 002.
Phone: (0866) 2429044

APCOB - MANGALAGIRI BRANCH, GUNTUR DISTRICT - INTERIOR WORKS

Sl. No.	Description	Nos.	Measurements			Qty	Unit	Rate (Incl. GST)	Amount (Incl. GST)
			L	B	D				
(A)	INTERIOR WORKS								
1	<p>False Ceiling (Gyp Board) - Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification, approval of the Bank. No Drop or design (if any) will be considered as extra measurement it will be considered flat ceiling. All as per the instructions of the Architects.</p>								
	At main Entrance	1	11.25	15.50	-	174.38			
	BM Room	2	10.00	1.50	-	30.00			
	BM Room	2	11.00	1.50	-	33.00			
	Banking Hall	2	40.00	2.00	-	160.00			
	Banking Hall	2	31.75	2.00	-	127.00			
	UPS Area	1	5.25	6.75	-	35.44			
						559.81	Sft		
2	<p>FALSE CEILING (24"x24" GRID FALSE CEILING)- 24"x24" Grid False Ceiling (SILHOULTE GRID): Providing and Fixing False Ceiling Grid using hot dipped Galvanized steel sections, exposed surface chemically cleaned capping pre-finished in baked polyester paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x 24mm at every 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x 600mm. The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/23 of 1987 , Noise reduction co-eff. (NRC) of 0.50, Light reflectance of 83%, Sound attenuation of 32db, thermal conductivity of k=0.052 W/m, wt of 4kgs/mts and humidity resistance of RH-95 , with paint finish of 600x600mm x 12mm thick over the Grid. All as per the design and instructions Architects.</p>								

	Bm Room	1	7.00	8.00	-	56.00			
	Banking Hall	1	40.00	31.75	-	1270.00			
	D/D Gyp area at Banking hall	-2	31.75	2.00	-	-127.00			
	D/D Gyp area at Banking hall	-2	40.00	2.00		-160.00			
	D/D Toilets area	-1	10.00	9.00		-90.00			
						949.00	Sft		
3	PARTITIONS - Providing and fixing 12mm thickness toughened glass partitions in position including all necessary Hardware as per the specification of Bank (Saint Gobain Glass).								
	(A). TOUGHENED GLASS PARTITION								
	FULL HT. PARTITION UP TO 9'-0" Height.								
	BM ROOM PARTITION	1	11.00	9.00	-	99.00			
	BM ROOM PARTITION	1	10.00	9.00	-	90.00			
	BM ROOM PARTITION	1	5.00	9.00		45.00			
	MAIN ENTRANCE	1	15.00	9.00		135.00			
	ATM ROOM	1	4.00	9.00	-	36.00			
	UPS PARTITIONS	1	5.25	7.00		36.75			
	LUNCH ROOM PART	1	7.00	9.00		63.00			
	LUNCH ROOM PART	1	10.00	9.00		90.00			
	DOORS FOR BM ROOM, UPS ROOM, LUNCH ROOM, 2ND MANAGER ROOM, RECORD ROOM	6	3.00	6.00		108.00			
	TOTAL					702.75	Sft		
4	CUSTOMISED STICKERING ON TOUGHENED GLASS							350.00	Sft
5	(A) PARTLY GLAZED PARTITION								
	(i). PARTLY GLAZED CASH CABIN PARTITION UP TO 7'- 0" HEIGHT BOTH SIDE LAMINATE FINISH								
	CASH CABIN	1	8.00	7.00	-	56.00			
						56.00	Sft		

	(ii). PARTLY GLAZED LOW HT. PARTITION UP TO 5'-0"X 4' -0"HT BOTH SIDE LAMINATE FINISH (OFFICER AND CLERK TABLE MIDDLE PARTITION)							
	CASH PARTITION	1	6.00	7.00	-	42.00		
	COUNTER PARTITION	1	22.50	1.50	-	33.75		
	LOW HT PARTITION	5	5.00	4.00	-	100.00		
						175.75	Sft	
	(B). 12mm THICK TOUGHENED GLASS CASH ENTRANCE							
	12mm THICK TOUGHENED GLASS CASH ENTRANCE							
	AT CASH COUNTER	1	6.50	7.00	-	45.50		
						45.50	Sft	
6	<p>TABLE - Providing and fixing tables made out of 19mm thk comm board of approved make clad with 1.0 mm laminate (color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden lipping's and moldings duly melamine polish. The drawers to be made out of 19mm thk comm. board duly laminated in the front, sides to be made out of 12mm comm. plyw and bottom to be made out of 6mm comm. ply and it should play in drawer sliding channels. The inside of the drawer and the table to be duly paint. A leg rest to be provided out of 3"x2" thk wooden section. A shutter to be made by 19mm comm. board clad with 1.0 mm laminate. The necessary locks handle to be provided in each drawers and shutters. On top of the Branch managers table 10mm thk glass to be placed duly edge polished. The table should have key board tray and tea tray duly finished with 1.0 mm laminate. The necessary wire managers to be provided on the tables and provision for lights to be kept if required in the front of the table.</p>							
	CPU trolley to be provided everywhere with a provision of castors to be provided .19mm comm. board & 12mm ply panel fix front side as per as per design including the raised level & perforations. The table have 12mm glass panel over wooden panel fix with SS Stud. All the exposed wooden areas to be duly melamine polished The work to be completed as per design and approval of the Architect							
	(A). MANAGER TABLE (SIZE:- 6'-0"x2'-6"x2'-6" HT,)							
		1	1.00	1.00	-	1.00		
						1.00	Nos.	
	(B). OFFICER AND SECOND OFFICERTABLE, (SIZE:-5'-6"x2'-6")							
		2	1.00	1.00	-	2.00		
						2.00	Nos.	

	(C). COUNTER TABLES, (SIZE:-4'-4"x2'-6")								
		4	1.00	1.00	-	4.00			
						4.00	Nos.		
	(D). COUNTER TABLE BESIDE CASH CABIN, (SIZE:-4'-6"x2'-6")								
		1	1.00	1.00	-	1.00			
						1.00	Nos.		
	(E). CASH COUNTER TABLE, (SIZE:-6'-0"x2'-6") with two side drawers								
		1	1.00	1.00	-	1.00			
						1.00	Nos.		
	(F) RUNNING COUNTER WITH DRAWER UNIT(UPS ROOM)								
	LUNCH ROOM AND UPS ROOM	1	10.00	1.00	-	10.00			
	RUNNING COUNTER	1	28.00	1.00		28.00			
						38.00	Rft		
7	Storage Side Unit - Providing and fixing Side Unit made out of 19mm comm. board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm comm. board in the front clad with 1.0mm laminate. sides to be made out of 12mm comm.ply and bottom made out of 6mm comm ply duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm comm. board and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit to be white laminate finish. All the exposed edges of the boards/ply woods to be covered with PVC edge bends. The work to be completed as per approval and specification of the Bank.								
	2nd Manager and Gold Appraiser counters	2	4.60	4.60	-	42.32			
	BM ROOM Side unit	1	3.60	1.60	-	5.76			
	BM Room Back unit	1	10.00	1.60		16.00			
						64.08	Sft		

10	WRITING LEDGE - Providing and fixing writing ledge as per design made out 19mm comm. board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. ply to be made on top of the writing ledge finished with 1.0 mm laminate, inside enamel painted .The work to be completed as per design and approval of the architect.								
						1.00	Nos		
13	Notice Board (4x3 ft) with pigeon racks, Suggestion Box and Cheque Deposit Box - Providing and fixing as per specifications of the Bank.								
						1.00	Nos		
16	VERTICAL BLINDS - Providing and fixing vertical blinds of 100mm lenth of vista Lavour of approved shade and pattern. The overlapping should be uniform and adequate. Necessary operative arrangements, frames0 to be provided. The work to be completed as per specification and approval of the architect.								
	AT WINDOW	6	4.00	4.50	-	108.00			
						108.00	Sft		
19	Shutter Box - Overhead outside shutter box: p/f sal/maranti wood frame fixing of 12mm plywood with 1mm thk. Laminate finish and openable shutter for outside area(for branch and atm)								
	Main Entrance	1	15.00	2.00	-	30.00			
	ATM Entrance	1	4.00	1.00	-	4.00			
						34.00	Sft		
20	DRESSING MIRROR with drawer unit (strong room) -Providing and fixing dressing table made out of mirror of size 2' 0" x 4' 0" using 12mm thk. Comm. Ply on back with 6mm thk. clear Mirror (First quality) approved make, fixed on the wall and tray of size 1' 6" x 1' 6"x 6" with one drawer for cosmetics. The mirror and ply should be fitted in Steam beach wooden molding of size 25mm x 25mm finished with melamine. Rate shall include necessary fixtures and hardware fittings for dressing mirror & drawer unit. (Measurement is measured only for mirror)								
	Dressing Mirror					1.00	Nos.		

21	Wall PANELLING - with 8mm thick BWR Ply fixed to 1" x 2" sal wood verticals and horizontals								
	CASH COUNTER PANELLING	2	6.50	7.00	-	91.00			
						91.00	Sft		
22	8mm Glass on Tables								
						6.00	Nos		
							TOTAL- -INTERIORS in Rs.		