



THE ANDHRA PRADESH STATE CO-OPERATIVE BANK Ltd.,

(A State Govt. Partnered Scheduled Bank)

HO: NTR Sahakara Bhavan, # 27-29-28, Governorpet, Vijayawada-520 002.

Url: <http://www.apcob.org> Email: premises@apcob.org

Date: 22.05.2023

TENDER NOTICE

Interior works in APCOB Kanuru Branch

Sealed Quotations are invited from GST registered firms for undertaking interior works tabulated below in Kanuru Branch of The A.P. State Co-operative Bank Ltd., at Vijayawada.

Time Schedule:

Quotation calling date - 22.05.2023

Quotation closing date - 25.05.2023 up to 10:30 AM

Quotation opening date - 25.05.2023 at 03.00 PM

Contact Person - DGM (GAD)

Note:

1. Valuation of work is subjected to actual measurements by Bank's consultant Civil Engineer.
2. The relevant Scope of Work is attached.

If your firm is interested in participation and having its Registered/Branch Office at Vijayawada with AP GST No., please submit your quotation (inclusive of all taxes) to :

M Shyama Sundara Rao

DY. GENERAL MANAGER (GAD)

THE A.P. STATE CO-OPERATIVE BANK LTD.,

HO: NTR Sahakara Bhavan, # 27-29-28, Governorpet, Vijayawada-520 002.

Phone: (0866) 2429044, 088, 7729996777

Sl. No.	Description	Nos	Measurements			Qty	Unit	Rate	Amount
			L	B	D				
(A)	Repairs to Interior work at APCOB Kanuru Branch/Vijayawada								
1	PARTITIONS - Providing and fixing partition in position as per design with 2" x 2" Maranti/Sal wood section finished frame work @ 2'0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil .The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be clad with 6mm thk comm. ply both side finished with approved 1.0 mm thk. laminate (color with vertical grain) as per design with adhesive and 3" high laminate skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 10 mm thk. Etched glass with sand blusting/granular blasting to be provided duly fixed with wooden lipping 37mm x 19 mm all complete duly polished. The work to be completed as per design approval of the architect. (Existing Damaged partiions Reapirs)								
	BM Room Partition	1	2.50	7.00	-	17.50			
	BM Room Partition	1	1.50	7.00	-	10.50			
	Partition at Wash area	1	4.50	8.25	-	37.13			
	D/d Door area	-1	3.00	7.00	-	-21.00			
	Back office Table Partition	1	5.00	6.00	-	30.00			
						74.13	Sft		
2	Labour Charges for Removing of Old Full/Low Height Partitions with Glass and refixing with alterations for Branch area including cost of al required materials and tools and palnts and all labour charges for fininsed item of work								
	BM Room Partition	1	2.50	7.00	-	17.50			
	BM Room Partition	1	1.50	7.00	-	10.50			
	Partition at Wash area	1	4.50	8.25	-	37.13			
	D/d Door area	-1	3.00	7.00	-	-21.00			
	Back office Table Partition	1	5.00	6.00	-	30.00			
	Table	1	4.50	2.50	-	11.25			
						85.38	Sft		

Sl. No.	Description	Nos.	Measurements			Qty	Unit	Rate	Amount
			L	B	D				
3	LHS- STORAGE - Providing and fixing Full height storage 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas . The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate(color, vertical grain) .sides to be made out of 12mm plywood and bottom made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels . The shutters to be made out of 19mm block board and should play on drawer sliding castors on powder coated channels. The necessary locks , handles, etc to be provided . 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas . Inside of the unit to be enamel painted in matching tone . All the exposed edges of the boards/plywoods to be covered with wooden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect.								
	at Cah counter	2	3.00	2.50	-	15.00			
	at Back office Table	1	3.25	2.50	-	8.13			
						23.13	Sft		
4	BACK OFFICE TABLE - Providing and fixing tables made out of 19mm thk comm board of approved make cladded with 1.0 mm laminate (color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden lipping's and moldings duly melamine polish. The drawers to be made out of 19mm thk comm. board duly laminated in the front, sides to be made out of 12mm comm. plyw and bottom to be made out of 6mm comm. ply and it should play in drawer sliding channels. The inside of the drawer and the table to be duly paint. A leg rest to be provided out of 3"x2" thk wooden section. A shutter to be made by 19mm comm. board cladded with 1.0 mm laminate. The necessary locks handle to be provided in each drawers and shutters. On top of the Branch managers table 10mm thk glass to be placed duly edge polished. The table should have key board tray and tea tray duly finished with 1.0 mm laminate. The necessary wire managers to be provided on the tables and provision for lights to be kept if required in the front of the table.								
	OFFICER AND SECOND OFFICERTABLE, (SIZE:-5'-6"x2'-6")								
		1	1.00	1.00	-	1.00			
						1.00	Nos.		
5	Repairs- Key Board Channes Repairs with New Channels to be provided everywhere with a provision of castors to be provided . 19mm comm. board & 12mm ply panel fix front side as per as per design including the raised level & perforations.								
	Key Board Channes Repairs with New Channels								
		2	1.00	1.00	-	2.00			
						2.00	Nos.		

